

OZ	Objekt	Bemerkung	Dokument	Komplexität	Anzahl	Stärke	Höhe	Länge	Umfang	Fläche	Volumen	Menge2
01.01.0001	Ausbauarbeiten\Estricharbeiten\Zementestrich Estrich auf Dämmschicht F4 D 45mm											
	Büro 0.01	<Erdgeschoss>		1,000	1,000 St	2,500 m			18,138 m	19,116 m²	47,789 m³	19,116 m²
	Büro 0.02	<Erdgeschoss>		1,000	1,000 St	2,500 m			19,201 m	22,281 m²	55,703 m³	22,281 m²
	Büro 1.01	<Erdgeschoss>		1,000	1,000 St	2,500 m			18,138 m	19,116 m²	47,789 m³	19,116 m²
	Büro 1.02	<Erdgeschoss>		1,000	1,000 St	2,500 m			19,201 m	22,281 m²	55,703 m³	22,281 m²
	Pos 001	<Erdgeschoss>		1,000	1,000 St	0,240 m	2,500 m	22,537 m		56,341 m²	13,522 m³	56,341 m²
	Pos 001.1	<Erdgeschoss>		1,000	1,000 St	0,240 m	1,260 m	4,009 m		5,051 m²	1,213 m³	-5,051 m²
	Pos 001.2	<Erdgeschoss>		1,000	1,000 St	0,240 m	1,260 m	4,011 m		5,054 m²	1,213 m³	-5,054 m²
	Pos 001.3	<Erdgeschoss>		1,000	1,000 St	0,240 m	1,260 m	4,011 m		5,054 m²	1,213 m³	-5,054 m²
	Pos 001.4	<Erdgeschoss>		1,000	1,000 St	0,240 m	1,260 m	4,011 m		5,054 m²	1,213 m³	-5,054 m²
	Pos 002	<Erdgeschoss>		1,000	1,000 St	0,240 m	2,500 m	0,510 m		1,275 m²	0,306 m³	1,275 m²
	Pos 003	<Erdgeschoss>		1,000	1,000 St	0,240 m	2,500 m	3,799 m		9,498 m²	2,279 m³	9,498 m²
	Pos 004	<Erdgeschoss>		1,000	1,000 St	0,240 m	2,500 m	17,779 m		44,447 m²	10,667 m³	44,447 m²
	Pos 005	<Erdgeschoss>		1,000	1,000 St	0,240 m	2,500 m	3,071 m		7,678 m²	1,843 m³	7,678 m²
	Pos 006	<Erdgeschoss>		1,000	1,000 St	0,240 m	2,500 m	4,809 m		12,022 m²	2,885 m³	12,022 m²
	Pos 007	<Erdgeschoss>		1,000	1,000 St	0,240 m	2,500 m	14,934 m		37,335 m²	8,960 m³	37,335 m²
	Pos 008	<Erdgeschoss>		1,000	1,000 St	0,240 m	2,500 m	10,339 m		25,848 m²	6,203 m³	25,848 m²
	Pos 008.1	<Erdgeschoss>		1,000	1,000 St	0,240 m	2,260 m	0,971 m		2,196 m²	0,527 m³	-2,196 m²
	Pos 009	<Erdgeschoss>		1,000	1,000 St	0,240 m	2,500 m	6,989 m		17,472 m²	4,193 m³	17,472 m²
	Pos 009.1	<Erdgeschoss>		1,000	1,000 St	0,240 m	0,760 m	4,010 m		3,048 m²	0,731 m³	-3,048 m²
	Pos 009.2	<Erdgeschoss>		1,000	1,000 St	0,240 m	0,760 m	2,009 m		1,527 m²	0,366 m³	-1,527 m²
	Pos 010	<Erdgeschoss>		1,000	1,000 St	0,240 m	2,500 m	22,537 m		56,341 m²	13,522 m³	56,341 m²
	Pos 010.1	<Erdgeschoss>		1,000	1,000 St	0,240 m	1,260 m	5,198 m		6,550 m²	1,572 m³	-6,550 m²
	Pos 010.2	<Erdgeschoss>		1,000	1,000 St	0,240 m	1,260 m	5,198 m		6,550 m²	1,572 m³	-6,550 m²
	Pos 010.3	<Erdgeschoss>		1,000	1,000 St	0,240 m	1,260 m	5,200 m		6,552 m²	1,573 m³	-6,552 m²
	Pos 010.4	<Erdgeschoss>		1,000	1,000 St	0,240 m	1,260 m	3,160 m		3,982 m²	0,956 m³	-3,982 m²
	Pos 011	<Erdgeschoss>		1,000	1,000 St	0,240 m	2,500 m	3,998 m		9,995 m²	2,399 m³	9,995 m²
	Pos 012	<Erdgeschoss>		1,000	1,000 St	0,240 m	2,500 m	3,801 m		9,503 m²	2,281 m³	9,503 m²
	Pos 013	<Erdgeschoss>		1,000	1,000 St	0,240 m	2,500 m	9,799 m		24,499 m²	5,880 m³	24,499 m²
												344,430 m²
01.01.0002	Ausbauarbeiten\Estricharbeiten\Trittschalldämmschicht PS-Hartschaum EPS LD-CP 30-2mm 30MN/m3 0,045W/mK											
	Büro 0.01	<Erdgeschoss>		1,000	1,000 St	2,500 m			18,138 m	19,116 m²	47,789 m³	19,116 m²
	Büro 0.02	<Erdgeschoss>		1,000	1,000 St	2,500 m			19,201 m	22,281 m²	55,703 m³	22,281 m²
	Büro 1.01	<Erdgeschoss>		1,000	1,000 St	2,500 m			18,138 m	19,116 m²	47,789 m³	19,116 m²
	Büro 1.02	<Erdgeschoss>		1,000	1,000 St	2,500 m			19,201 m	22,281 m²	55,703 m³	22,281 m²
												82,794 m²
01.01.0003	Ausbauarbeiten\Estricharbeiten\Abdeck. PE-Folie											
	Büro 0.01	<Erdgeschoss>		1,000	1,000 St	2,500 m			18,138 m	19,116 m²	47,789 m³	20,071 m²
	Büro 0.02	<Erdgeschoss>		1,000	1,000 St	2,500 m			19,201 m	22,281 m²	55,703 m³	23,395 m²
	Büro 1.01	<Erdgeschoss>		1,000	1,000 St	2,500 m			18,138 m	19,116 m²	47,789 m³	20,071 m²
	Büro 1.02	<Erdgeschoss>		1,000	1,000 St	2,500 m			19,201 m	22,281 m²	55,703 m³	23,395 m²
												86,932 m²
01.01.0006	Ausbauarbeiten\Estricharbeiten\Betonstahlgitter											
	Büro 0.01	<Erdgeschoss>		1,000	1,000 St	2,500 m			18,138 m	19,116 m²	47,789 m³	20,071 m²
	Büro 0.02	<Erdgeschoss>		1,000	1,000 St	2,500 m			19,201 m	22,281 m²	55,703 m³	23,395 m²
	Büro 1.01	<Erdgeschoss>		1,000	1,000 St	2,500 m			18,138 m	19,116 m²	47,789 m³	20,071 m²
	Büro 1.02	<Erdgeschoss>		1,000	1,000 St	2,500 m			19,201 m	22,281 m²	55,703 m³	23,395 m²
												86,932 m²
01.03.0002	Ausbauarbeiten\Putzarbeiten\Kante Innenputz Profil Kunststoff D 15mm											
	Büro 0.01	<Erdgeschoss>		1,000	1,000 St	2,500 m			18,138 m	19,116 m²	47,789 m³	15,000 m
	Büro 0.02	<Erdgeschoss>		1,000	1,000 St	2,500 m			19,201 m	22,281 m²	55,703 m³	15,000 m
	Büro 1.01	<Erdgeschoss>		1,000	1,000 St	2,500 m			18,138 m	19,116 m²	47,789 m³	15,000 m
	Büro 1.02	<Erdgeschoss>		1,000	1,000 St	2,500 m			19,201 m	22,281 m²	55,703 m³	15,000 m
												60,000 m
01.03.0004	Ausbauarbeiten\Putzarbeiten\Innenputz einlagig Innenwand PIV D 15mm Q2 gerieben											
	Büro 0.01	<Erdgeschoss>		1,000	1,000 St	2,500 m			18,138 m	19,116 m²	47,789 m³	45,346 m²
	Büro 0.02	<Erdgeschoss>		1,000	1,000 St	2,500 m			19,201 m	22,281 m²	55,703 m³	48,002 m²
	Büro 1.01	<Erdgeschoss>		1,000	1,000 St	2,500 m			18,138 m	19,116 m²	47,789 m³	45,346 m²
	Büro 1.02	<Erdgeschoss>		1,000	1,000 St	2,500 m			19,201 m	22,281 m²	55,703 m³	48,002 m²
												186,696 m²
01.04.0003	Ausbauarbeiten\Tapezierarbeiten\Tapezieren Wand Papierwandbekl.											
	Büro 0.01	<Erdgeschoss>		1,000	1,000 St	2,500 m			18,138 m	19,116 m²	47,789 m³	45,346 m²
	Büro 0.02	<Erdgeschoss>		1,000	1,000 St	2,500 m			19,201 m	22,281 m²	55,703 m³	48,002 m²
	Büro 1.01	<Erdgeschoss>		1,000	1,000 St	2,500 m			18,138 m	19,116 m²	47,789 m³	45,346 m²
	Büro 1.02	<Erdgeschoss>		1,000	1,000 St	2,500 m			19,201 m	22,281 m²	55,703 m³	48,002 m²
												186,696 m²

